Carlson

SPECIFICATIONS

1. Two roof swamp coolers, instead of wall units, to be installed with air flow into the main hallway.

2. Front and rear entry doors with concrete and metal stairways.

3. Carpet to be obtained from Carpet Mart, 171 East 900 South, Provo, Utah, @ $6.75 per yard laid:

a) Brand name:

b) Colors:

c) Installation:

4. Cabinets:

5. Countertops:

6. All four ranges and refrigerators to be harvest gold, General Electric Company products.

7. Linoleum:

8. Building to be constructed entirely of brick.

9. Four stainless steel sinks.

10. Six inch (6") to eight inch (8") insulation in roof.

11. Three and one-half inch (3 1/2) insulation in walls and floors.

12. Four 40 gallon water heaters.